



LAND BANK OF THE PHILIPPINES
INCORPORATED IN THE PHILIPPINES
BANK OF THE PEOPLE

BID BULLETIN NO. 1
For ITB No. 2015-3-104

PROJECT : **Supply, Delivery & Installation of New Horizontal & Vertical Panagraphics Signages and Modification/Refacing of Existing Signages at Various LANDBANK Branches/Offices**

IMPLEMENTOR : **Procurement Department**

DATE : **July 9, 2015**

This Bid Bulletin is issued to modify or amend items in the Bid Documents. This shall form an integral part of the Bid Documents.

The modification or amendment is as follows:

- Project timetable for the 53 New Horizontal Signages at 49 LANDBANK Branches/Offices has been revised. Please see attached revised Annex V2.

For guidance and information of all concerned.


ALWIN I. REYES
Department Manager
Procurement Department

- d) Supply and installation of new led type lighting fixtures – refer to **Annex A-2** for detailed specifications on the coverage of the LED lighting fixture. (See **Annex A-3** Photo reference for the final result of lighting effect)
- e) Guarantee for services provided:
 - 1. Warranty for a full five (5) years on the translucent film color
 - 2. Performance and durability, and on the flexible substrate against blowout and mildew resistance and three (3) years warranty against any defect in product and workmanship from converter
- f) Flexible substrate film and translucent film must be seamless.
- g) Graphics cutting of Scotchcal Translucent Film shall be done with computer cutter – *manual cutting is unacceptable and shall not be allowed*
- h) Shop drawing (based on actual dimensions – see note 1) for each of the branches' signage, and one prototype shall be submitted to PMED for review and approval prior to production/fabrication. Same must be printed in A4 size paper with the supplier's official letterhead.
- i) List of branches to be dismantled of existing signage and installed with new units along with their corresponding estimated sizes/dimensions attached as **Annex A-4**

Note:

- 1. *Actual dimensions (height and length) for each panagraphics signage shall be verified by the supplier on site/branch.*
- 2. *A Certification of Inspection Conducted duly noted by the branch manager shall be attached with the shop drawings.*
- j) Pre- and Post-installation inspections by PMED will be done in the supplier's warehouse/plant/shop and on-site/branch respectively to determine compliance with LANDBANK plans and specifications.
- k) Acknowledgement Receipt/Inspection Report or ARIR (**sample attached as Annex A-5**), duly signed by the Branch Manager, shall be submitted by the supplier which will be required in the processing of payments.
- l) Non-compliant signage shall be immediately rectified and/or replaced by suppliers within 7 calendar days upon receipt of notification from PMED.
- m) A logo kit (consists of the standard design for signage, and logo samples – in cd and print) will be provided by CAD to the supplier to which they should faithfully adhere.

I. Project Timetable

Deliverables	Time Frame (Calendar days) ¹
Submission of shop drawings and mock-up	10
Production²	75

Revised
VE